

SCHEDULE 1 – DESCRIPTION OF HIGHWAY WORKS

The works shall comprise the construction of the following:

1. Kassell style "level entry" high kerbs, tactile paving, pole and flag and associated footway works to be provided at the north bound bus stop adjacent to 171 Warley Hill;
2. Kassell style "level entry" high kerbs, tactile paving, a replacement shelter, pole and flag and associated footway works to be provided at the south bound bus stop opposite Hill Crest in Warley Road.
3. Construction of a 3 metres wide Cyclepath/ footpath link between the estate road serving the development and Greensleeves Drive, Clements Park to the North of the Site, including lighting, drainage and measures to prevent its use by motorised vehicles;